

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21282-00-00

Spot: SWSWSW

Sec/Twnshp/Rge: 11-15S-14W

330 feet from S Section Line,

330 feet from W Section Line

Lease Name: LYDIA KRUG

Well #: 1

County: RUSSELL

Total Vertical Depth: 3343 feet

Operator License No.: 3134

Op Name: MORRIS, TERRY E. DBA G L M COMPA

Address: PO BOX 193

RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	883	0	NO SXS LISTED
PROD	5.5	3340	0	250 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/05/2011 12:30 PM

Plug Co. License No.: 34071

Plug Co. Name: PATRIOT WELL SERVICE, INC.

Proposal Rcvd. from: TERRY MORRIS

Company: G L M COMPANY

Phone: (785) 483-1307

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perf: 1200' - 885' - 325'.

Plugging Proposal Received By: RAY DINKEL

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 07/05/2011 4:30 PM

KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2900' - pumped 150 sxs cement with 300# hulls.
Pulled tubing 1400' - pumped 145 sxs cement with 200# hulls - cement circulated.
POOH. Hooked to casing - pumped 20 sxs cement.
Max. P.S.I. 500#.
Hooked to Braden head and pumped 5 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3340	3343		OH ARBUCKLE

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4669.

RECEIVED

JUL 15 2011

Plugged through: TBG

KCC WICHITA

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

Form CP-2/3

JUL 07 2011