

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-07520-00-00  
Spot: NESWNE Sec/Twnshp/Rge: 34-20S-12W  
3630 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: LANGREHR Well #: 3  
County: BARTON Total Vertical Depth: 3395 feet

Operator License No.: 7383  
Op Name: GRADY BOLDING CORPORATION  
Address: PO BOX 486  
ELLINWOOD, KS 67526

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF   | 8.625 | 265        | 0           | 200 SX   |
| PROD   | 5.5   | 3392       | 0           | 100 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/24/2011 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: GRADY BOLDING Company: GRADY BOLDING CORPORATION Phone: (620) 564-2240

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 300# hulls - 11 sxs gel.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/24/2011 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perfed at 1500' and 650'.  
Ran tubing to 3200' - tied onto tubing - pumped 11 sxs gel - followed with 75 sxs cement with 200# hulls.  
Pulled tubing to 1500' - pumped 100 sxs cement:  
Pulled to 680' - pumped 70 sxs cement with 100# hulls - circulated casing to surface.  
Pulled tubing. Topped off with 20 sxs cement.  
Tied to surface pipe - pressured to 200# P.S.I. - would not take any more cement.

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #36839.

Plugged through: CSG

RECEIVED

JUL 15 2011

KCC WICHITA

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

Form CP-2/3

JUN 29 2011