

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19277-00-04]
Spot: NESESE Sec/Twnshp/Rge: 17-11S-15W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: STEWART Well #: 1
County: RUSSELL Total Vertical Depth: 2725 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/29/2011 12:00 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: Company: BEREXCO LLC Phone: (316) 265-3311

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 07/10/2011 9:45 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

06/29/2011 - Old 8 5/8" casing found at 30'. 4' x 4' plate welded on casing with 7" casing extended 9' below plate to surface. Moved in rig.
06/30/2011 - Started drilling. Mudded up. Lost and poor circulation from the start. Soft and hard drilling from 50'. Hard drilling at 273'. Hard drilling to 650' - pushing wood.
07/08/2011 - Pulled out 6 1/4" bit and ran in 4 7/8" blade bit.
Hit bridges getting back to 650'. Circulation lost several times getting down. Got easy drilling from 670' down to 2725'.
07/09/2011 - Shot off bit and perforated two holes at 2715'. Pumped 100 sxs 60/40 pozmix - 4% gel cement and 200# cotton seed hulls.
07/10/2011 - Pulled tubing to 1690' and perforated two holes and pumped 150 sxs cement with 200# hulls.
Pulled to 1045' and perforated two holes and pumped 150 sxs cement with 200# hulls - fluid circulating.
Pulled tubing to 488'. Perforated two holes at 500' and pumped 255 sxs cement with 200# hulls - cement circulated.
POOH. Topped off with 30 sxs cement. Hole stayed full.
Finished plugging at 9:45 a.m.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

RECEIVED

JUL 15 2011 CP-2/3

KCC WICHITA

JUL 11 2011