

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21278-00-00
Spot: SWNWNENE Sec/Twnshp/Rge: 33-9S-26W
496 feet from N Section Line, 1245 feet from E Section Line
Lease Name: JAMISON Well #: 2
County: SHERIDAN Total Vertical Depth: 4200 feet

Operator License No.: 30076
Op Name: ANDERSON, ANDY DBA A & A PRODU
Address: PO BOX 100
HILL CITY, KS 67642

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	237	0	w/160 sxs cmt
PROD	4.5	4155	0	w/160 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/06/2011 1:30 PM
Plug Co. License No.: 33612 Plug Co. Name: GEIST, RON DBA WILDCAT WELL SERVICE
Proposal Rcvd. from: ANDY ANDERSON Company: A & A PRODUCTION Phone: (785) 421-6266

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
Plug through casing.

Plugging Proposal Received By: CASE MORRIS Witness Type: PARTIAL
Date/Time Plugging Completed: 07/06/2011 9:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 237' w/160 sxs cement.
4 1/2" production casing set at 4155' w/160 sxs cement.
Port collar set at 2287' was not cemented. Well non-commercial.
Operator reported that perforations sanded back and plug placed with dump bailer.
Bottom plug was not witnessed by KCC staff.
Casing cut at 2501' and 2334'. Casing could not be pulled.
Connected to 4 1/2" production casing and pumped 150 sxs cement mixed with 200# hulls.
Displaced cement to 1400'.
Cut 4 1/2" production casing at 1355'. Casing free. Pumped 100 sxs cement mixed with 200# hulls.
Pulled 4 1/2" production casing to 280' - pumped 90 sxs cement mixed with 100# hulls - cement to surface.
Pulled 4 1/2" production casing to surface.
Cellar was full of cement and filled surface casing as 4 1/2" was pulled.
Plug complete.

Perfs:

Top	Bot	Thru	Comments
3916	3920		
3906	3909		
3875	3878		

Remarks: ALLIED CEMENTING COMPANY-TICKET #43440.

Plugged through: CSG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

RECEIVED
Form CR-2/3
JUL 15 2011

JUL 07 2011

KCC WICHITA