

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-22517-00-00  
Spot: SENEWNE Sec/Twnshp/Rge: 21-14S-22W  
1820 feet from N Section Line, 1340 feet from E Section Line  
Lease Name: HONAS 'EF' Well #: 1-21  
County: TREGO Total Vertical Depth: 4210 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 N MARKET STE 300  
WICHITA, KS 67202

| String | Size  | Depth (ft) | Pulled (ft) | Comments      |
|--------|-------|------------|-------------|---------------|
| SURF   | 8.625 | 219        | 0           | 160 SX CEMENT |
| T1     | 2.375 | 3750       |             |               |
| PC     |       | 1647       |             |               |
| PROD   | 4.5   | 4209       | 0           | 185 SX CEMENT |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/12/2011 1:00 PM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: BILL Company: PINTAIL PETROLEUM, LTD. Phone: (785) 263-2243

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 200# hulls - 10 sxs gel.  
Port collar at 1647' w/125 sxs.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/12/2011 5:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto backside - pumped 15 sxs cement. S.I.P. 200#.  
Ran tubing to 3990' - pumped 10 sxs gel - followed with 60 sxs cement and 200# hulls.  
Pulled tubing to 2316' - pumped 155 sxs cement - good circulation of cement.  
Pulled tubing out - topped off with 20 sxs cement - full.

Perfs:


| Top  | Bot  | Thru | Comments      |
|------|------|------|---------------|
| 4130 | 4135 |      | CHEROKEE SAND |

Remarks: SWIFT CEMENTING COMPANY-TICKET #20963.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

RECEIVED

JUL 18 2011

CM

CP-2/3

JUL 14 2011

KCC WICHITA