

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21563-00-01
Spot: NENWSW Sec/Twnshp/Rge: 33-34S-41W
2555 feet from S Section Line, 3964 feet from E Section Line
Lease Name: WILBURTON MORROW SAND Well #: 1705W
County: MORTON Total Vertical Depth: 5050 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4725		WITH 2 SX CMT
CIBP		4935		
SURF	8.625	1466		WITH 420 SX CMT
PROD	5.5	5050	2521	WITH 415 SX CMT

Well Type: EOR UIC Docket No: _____ Date/Time to Plug: 06/30/2011 12:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CIBP @ 4725' WITH 2 SX CMT. SHOOT CASING CIRCULATE HOLE WITH MUD. PLUG AT 1490' WITH 50 SX CMT. PLUG AT 500' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/30/2011 4:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 4725' WITH 2 SX CMT. SHOT CASING AT 2521'. POOH TO 1490'.
CIRCULATE HOLE WITH MUD. 1ST PLUG AT 1490' WITH 50 SX CMT. 2ND PLUG
AT 500' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4940	4941		
4885	4890		
4873	4899		
4872	4882		
4860	4865		
4854	4859		
4810	4811		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED
JUL -7 2011
KCC DODGE CITY

Signed

Jack MacLaren
(TECHNICIAN)

RECEIVED
JUL 18 2011

Oct 16 7:19 AM
KCC WICHITA