

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21205-00-00
Spot: N2S2SWNE Sec/Twnshp/Rge: 20-35S-43W
3115 feet from S Section Line, 1980 feet from E Section Line
Lease Name: BOALDIN Well #: 2-20
County: MORTON Total Vertical Depth: 4736 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1393		WITH 725 SX CMT
DVT		4024		WITH 225 SX CMT
PROD	5.5	4733	1473	WITH 100 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/23/2011 9:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PERFORATE TBG & PUMP CMT. CUT TOP OF TBG. SHOOT & POOH WITH CASING. RIH W/TBG TO 1440' & PUMP 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 300' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/23/2011 1:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

TBG STUCK IN HOLE. TOC @ 3000 PEFORATE TBG @ 2200' & PUMPED 55 SX CMT. CUT TBG OFF. TAGGED TOC @ 1950'. SHOT 5 1/2" & POOH WITH CASING. RIH W/TBG & CIRCULATED HOLE WITH MUD. PUMPED 50 SX CMT AT 1440'. PUMP 40 SX CMT AT 600'. PUMP 30 SX CMT AT 300'. PUMP 10 SX CMT AT 40'.

Perfs:

Top	Bot	Thru	Comments
4582	4590		KEYES
4288	4300		MORROW SQD 100

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: TBG

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED

JUL 18 2011

KCC WICHITA

RECEIVED

JUN 29 2011

KCC DODGE CITY