

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21658-00-00

Spot: NENWNE

Sec/Twnshp/Rge: 13-34S-40W

4970 feet from S Section Line, 1660 feet from E Section Line

Lease Name: HENSHAW A

Well #: 1

County: MORTON

Total Vertical Depth: 6650 feet

Operator License No.: 5447

Op Name: OXY USA INC.

Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1748		WITH 750 SX CMT

PC		3118		
PROD	5.5	6650	1069	WITH 440 SX CMT

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 06/27/2011 1:30 PM

Plug Co. License No.: 32833

Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.

Proposal Rcvd. from: KIRBY LILLARD

Company: SARGENT LILLARD CASING PULL Phone: (580) 251-1881

Proposed Plugging Method: 200# HULLS & 25 SX CMT AT 6125'. PLUG AT 1800' WITH 25 SX CMT INSIDE 5 1/2". 30 SX CMT AT CASING STUB. 40 SX CMT AT 540'. 10 SX CMT AT 40'.

Plugging Proposal Received By: KEN JEHLIK

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/27/2011 4:30 PM

KCC Agent: JACK MACLASKEY

Actual Plugging Report:

Perfs:

CMT BOND LOG SHOW TOC @1500'. 6/26/11: PUMP 200# HULLS & 25 SX CMT AT 6125'. 6/27/11: RIH W/WIRELINE & TAGGED TOC @ 5810'. FILLED HOLE WITH MUD TO 1800' & PUMPED 25 SX CMT. SHOT 5 1/2" AT 1069'. CIRCULATED HOLE WITH MUD. PUMPED 30 SX CMT AT 1069'. PUMPED 40 SX CMT AT 540'. PUMPED 10 SX CMT AT 40'.

Top	Bot	Thru	Comments
6156	6205		MORROW

Remarks: USED COMMON CEMENT BY SARGENT LILLARD

Plugged through: CSG

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED

JUN 29 2011

KCC DODGE CITY

RECEIVED

JUL 18 2011

KCC WICHITA

Form CP-273