

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-179-20681-00-00  
Spot: SESWSENE Sec/Twnshp/Rge: 11-9S-27W  
2755 feet from S Section Line, 825 feet from E Section Line  
Lease Name: BREEDEN Well #: 4  
County: SHERIDAN Total Vertical Depth: 4175 feet

Operator License No.: 8914  
Op Name: H & C OIL OPERATING INC.  
Address: PO BOX 86  
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	344	0	200 sx
T1	2.875	4052	0	
PROD	5.5	4170	0	190 sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/11/2011 10:30 AM  
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC  
Proposal Rcvd. from: CHARLES R. RAMSEY Company: H & C OIL OPERATING INC. Phone: (785) 434-7434

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 12 sxs gel spacer.  
Perfed at 1427' and 2314'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/11/2011 2:30 PM KCC Agent: PAT BEDORE

**Actual Plugging Report:**

Ran tubing to 3866' - pumped 12 sxs gel spacer - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled tubing to 2342' - pumped 210 sxs 60/40 pozmix - 4% gel with 300# hulls to circulate to surface.  
Pulled all tubing. Topped off 5 1/2" casing with 20 sxs 60/40 pozmix - 4% gel.  
Hooked to 8 5/8" x 5 1/2" annulus. Pumped 70 sxs 60/40 pozmix - 4% gel.  
No pressure.

**Perfs:**

Top	Bot	Thru	Comments
3916	4018		LKC

Remarks: ALLIED CEMENTING COMPANY-TICKET #39748.

Plugged through: TBG

District: 04

Signed Pat Bedore  
(TECHNICIAN) CM

RECEIVED  
JUL 18 2011  
Form CP-2/3

JUL 14 2011

KCC WICHITA