

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02549-00-01
Spot: SWNWNWSW Sec/Twnshp/Rge: 36-12S-18W
2298 feet from S Section Line, 4955 feet from E Section Line
Lease Name: SCHMIDT Well #: 4
County: ELLIS Total Vertical Depth: 3647 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N MARKET STE 1130
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3405		
SURF	8.625	215	0	135 SX
PROD	5.5	3605	0	350 SX

Well Type: EOR UIC Docket No: E09694.1 Date/Time to Plug: 07/13/2011 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: SHANNON RAYBERN Company: EDMISTON OIL COMPANY, INC. Phone: (316) 265-5241

Proposed Plugging Method: Ordered 310 sxs 60/40 pozmix - 4% gel - 500# hulls - 7 sxs gel spacer.
DV at 2100' w/350 sxs.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/13/2011 12:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 2869' - pumped 7 sxs gel - followed with 50 sxs cement and 150# hulls.
Pulled tubing to 1866' - pumped 200 sxs cement - good circulation of cement.
Pulled tubing out - topped off with 40 sxs cement.
Tied onto backside - pumped 20 sxs cement - full - shut in 200# P.S.I.

Perfs:


Top	Bot	Thru	Comments
3629	3633		ARBUCKLE
3619	3624		ARBUCKLE
3571	3576		LANSING
3558	3565		LANSING
3534	3546		LANSING
3509	3514		LANSING

Remarks: CONSOLIDATED ACID AND CEMENTING COMPANY-TICKET #28088.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED

JUL 18 2011

KCC WICHITA

Form CP-2/3

cc to UIC 7/19

JUL 14 2011