

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21608-00-00
Spot: SESESW Sec/Twnshp/Rge: 18-13S-19W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: DISNEY Well #: 1-18
County: ELLIS Total Vertical Depth: 3815 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	224	0	145 SX
PROD	4.5	3810	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/13/2011 11:30 AM
Plug Co. License No.: 5112 Plug Co. Name: MIDWESTERN WELL SERVICE, INC.
Proposal Rcvd. from: CURT GABEL Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: Ordered 335 sxs 60/40 pozmix - 4% gel - 500# hulls.
Shoot perms 2050' and 1450'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/13/2011 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3408' - pumped 100 sxs cement with 250# hulls.
Pulled tubing to 2000' - pumped 160 sxs cement - good circulation.
Pulled tubing out - topped off with 25 sxs cement.
Tied onto backside - full - hit 500# P.S.I.

Perfs:

Top	Bot	Thru	Comments
3505	3508		
3462	3467		
3411	3414		
3348	3352		

Remarks: ALLIED CEMENTING COMPANY-TICKET #35917.

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN) CM

RECEIVED
JUL 18 2011 Form CP-2/3

JUL 14 2011

KCC WICHITA