

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15430-00-00
Spot: NWSESW Sec/Twnshp/Rge: 21-17S-14W
990 feet from S Section Line, 3630 feet from E Section Line
Lease Name: KEENAN B Well #: 4
County: BARTON Total Vertical Depth: 3377 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	864	0	500 SX
PROD	5.5	3368	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/11/2011 8:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls.
Perf: 815' - 1520'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/11/2011 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3145' - pumped 75 sxs cement with 200# hulls.
Pulled tubing to 2000' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 950' - pumped 110 sxs cement - cement circulated.
POOH. Topped off casing with 10 sxs cement - casing was full.
Hooked to Braden head and pumped 10 sxs cement.
Max. P.S.I. 200#.

Perfs:

Top	Bot	Thru	Comments
3255	3288		
3215	3218		
3184	3187		
3170	3173		
3115	3119		
3106	3110		
2974	2980		

Remarks: ALLIED CEMENTING COMPANY-TICKET #35912.

Plugged through: TBG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

RECEIVED
JUL 18 2011

KCC WICHITA

JUL 14 2011