



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

RECEIVED  
STATE CORPORATION COMMISSION

DEC 9 1974  
12.9-74  
CONSERVATION DIVISION  
Wichita, Kansas

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Russell Weston of Phillips Petroleum Company has this

date requested permission to plug the following described well:

Mr. Weston guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Company,

Complete Address: P. O. Box #358, Borger, Texas.

Lease Name: Byerly Well No. A-1

Location: 1980' FNL & 1980' FWL of Sec. 11 Twp. 18 Rge. (E)(W) 40

County: Greeley Total Depth 4250' Oil Well \_\_\_\_\_

Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X Lost Hole \_\_\_\_\_

Mr. Weston was instructed to plug the well as follows:

1430'--8 5/8" Surface casing, cement circulated.

Circulate hole with heavy mud. Pull DP to 2975' and displace 60 Sx. cement thru DP. Pull DP to 900' and displace 50 Sx. cement thru DP. Pull DP to 550' and displace 35 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 15 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent