



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 5 1974
3-5-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. R. L. Higginbottom of Dorchester Exploration, Inc. has this

date requested permission to plug the following described well:

Mr. Higgin bottom guarantees payment of the plugging fee.

Operator's full Name: Dorchester Exploration, Incorporated,

Complete Address: 1204 Vaughn Building, Midland Texas.

Lease Name: Brinkman Well No. 1

Location: CSW/4 Sec. 29 Twp. 18 Rge. (E)(W) 40

County: Greeley Total Depth 3000' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Higginbottom was instructed to plug the well as follows:

240'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 1025'.

Circulate hole with heavy mud. Pull DP to 1250' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 250' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

Conservation Division Agent