



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

9-26-82

RECEIVED
OCT 01 1982
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM

(To be filed by Plugging Agent)

15-171-20,237-0000

Dear Sir:

Mr. Wilmer Driley of Alecrombie Drilling Co. has this

date requested permission to plug the following described well:

Operator's Full Name: White & Ellis Drilling Inc.

Complete Address: Box 448 Eldorado Kansas 67042

Lease Name: Grothausen Grothausen Well No. 1

Location: C-NW-SE-NW Sec. 29 Twp. 16 Rge. 31 (E) (47)

County: Scott Total Depth: 4662'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Driley was instructed to plug the well as follows:

8 5/8 surface @ 386' cement circulated with 220 lbs common
cmt. 2 3/4 gells 3% CC. 1st plug @ 1200' w/ 70 lbs cmt. 2nd
plug @ 380' w/ 40 lbs cmt. 3rd plug 40' to on solid
bridge w/ 10 lbs cmt. 10 lbs cmt in rat hole. Cement
used was 50/50 plus mix 2 3/4 gells 3% CC. The cement was
pumped through drill pipe with hole full of heavy mud.

Very truly yours,

Paul A. Luthi

Conservation Division Agent

orders given by Bud Metz.