



15171-20077-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 18 1975
3-18-75
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Don Svinger of Abercrombie Drilling Inc. has this date requested permission to plug the following described well:

Mr. Don Svinger guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling Inc. & Beren Corp.

Complete Address: 801 Union Center, Wichita Ks

Lease Name: Swilley "A" Well No. #1

Location: C-N-W-NE Sec. 15 Twp. 16 Rge. 31 (E) (W) (W)

County: Scott Total Depth 4744' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Don Svinger was instructed to plug the well as follows:

- Pump down drillstem
- 70 sx cem. 50% Poz mix 6% Gel @ 1700'
- 20 " " " " " " @ 250'
- 1 sx Halls & Plug To 40'
- 10 sx cem 50% Poz mix 6% Gel on Top

Very truly yours,

Julius Balthazar
Conservation Division Agent