



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 24 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Delaney of Leben Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Yucca Petroleum Company,

Complete Address: P. O. Box #2585, Amarillo, Texas.

Lease Name: DeWeese Well No. 1

Location: CNW-SE Sec. 6 Twp. 16 Rge. (E)(W) 32

County: Scott Total Depth 4880' Oil Well

Gas-Well Input Well SWD-Well D & A X Lost Hole

Mr. Delaney was instructed to plug the well as follows:

395'--8 5/8" Surface casing, cement circulated with 270 Sx.
Top of Dakota section @ 1194'.

Circulate hole with heavy mud. Pull DP to 1500' and displace 100 Sx.
cement thru DP. Pull DP to 450' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent