

State of Kansas



1517130062-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1966
8-17-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Don Rider of K & E Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Rider guarantees payment of the plugging fee.

Operator's full Name: Westmore Drilling Company, Incorporated,

Complete Address: Chapin Building, Medicine Lodge, Kansas.

Lease Name: Koehn Well No. 1

Location: Appr. CSE Sec. 11 Twp. 16 Rge. (E)(W) 34

County Scott Total Depth 2900 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rider was instructed to plug the well as follows:

282'--8 5/8" Surface pipe, cement circulated with 200 Sx.

Circulate hole with heavy mud, set plug @ 600' and 25 Sx. cement.

" " 275' with 1/4 sk. hulls & 20 Sx. cement.
" " 40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

W. L. Nichols
Conservation Division Agent