


15-053-19126-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Ellsworth County. Sec. 5 Twp. 14 S Rge. (E) 9 (W)
Location as "NE/CNW%SW%" or footage from lines Ctr. SW/4
Lease Owner Messman-Rinehart Oil Company
Lease Name Foran Well No. 1
Office Address 518 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 20 19 60
Application for plugging filed March 30 19 61
Application for plugging approved March 9 19 61
Plugging commenced March 16 19 61
Plugging completed March 23 19 61
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gib Toman, Holyrood, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2230 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	277'	none
				4-1/2"	1548'	969'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole to 270 ft., set 10 ft. rock bridge, mixed and ran 20 sx. cement with dump bailer. Mud to 40 ft., set 10 ft. rock bridge with 10 sx. cement to base of cellar.


RECEIVED
STATE CORPORATION COMMISSION
APR 19 1961
04-19-61
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc - License No. 399
Address P. O. Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) *J. A. Gilliland*
518 Petroleum Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of April, 19 61
Barbara J. Scott
Barbara J. Scott, Notary Public.

My commission expires December 1, 1964



NO. 1 FORAM

Well Log:

Location:	Ctr. SW/4, Section 5-145-9W Ellsworth County, Kansas	Commenced:	April 28, 1960
Operator:	Hessman-Rinehart Oil Company 518 Petroleum Building Wichita, Kansas	Completed:	May 7, 1960 (Rotary)
Contractor:	Hessman-Rinehart Oil Company 518 Petroleum Building Wichita, Kansas	Elevation:	1710' K/S
		Production:	Gas

Casing Record: 8-5/8" @ 277' w/150 sk. com.,
4 gal., 3 c.c.
4-1/2" @ 1540' w/125 sk. com., 2 gal.
*** LOG ***

Clay	30
Sand	40
Shale & Clay	180
Red Bed	277
Red Bed & shale	380
Iron sulphate	400
Clay & shale	540
shale, shells & salt	960
shale & salt	1115
Anhydrite	1270
shale	1305
Sandy Lime & Shale	1460
Lime	1595
Lime & shale	1615
Lime	1800
Lime	1935
Lime & shale	2080
Sandy Lime & shale	2120
Sand - Lime - shale	2125
Sand & Lime	2230 R.T.D.

Sample Top:
2162 - Tarkio Lime (-452)

The undersigned, HESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

HESSMAN-RINEHART OIL COMPANY
By: J. A. Gilliland
J. A. Gilliland

Subscribed and sworn to before me
this 27th day of July, 1960.

By: Barbara J. Scott
Barbara J. Scott, Notary Public

My Commission Expires: December 1, 1960



COMPLETION DATA

Nessman-Rinehart Oil Company
 No. 1 Foran
 Ctr. SW/4, Sec. 5-14S-9W
Ellsworth County, Kansas

- 5/16/60 - Moved in cable tools, Perf. 1398-1406' w/24" E-gun, no show,
 Treated with 200 gal. mud acid, faint show gas, 1½ bbls. wtr./2 hrs.
- 5/17/60 Perf. 1309-11' w/4", no show
 Perf. 1416-20' w/8", no show
 Perf. 1452-56' w/6", no show
 Perf. 1334-38' w/6", no show
- 5/18/60 Set L-W Plug @ 1320 ft.
 Perf. 1282-94' w/22", 500 gal. mud acid, fair show gas,
 1000 gal. 15% acid
- 5/19/60 - Snabbed back 34,000 cfg
- 5/20/60 - Snabbing 150,000 cfg.,
 Completed well - to shut in awaiting connection.

NESSEMAN-RINEHART OIL COMPANY

By: Roger L. Nessman
 Roger L. Nessman, Partner

RLM/bjs
 7/27/60

RECEIVED
 STATE CORPORATION COMMISSION

APR 19 1961

CONSERVATION DIVISION
 Wichita, Kansas