

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-109-20689-00-00

LEASE NAME TEETER

WELL NUMBER 1

330 Ft. from N Section Line

990 Ft. from E Section Line

SEC. 10 TWP. 13 RGE. 32 (E) or (W)

COUNTY LOGAN

Date Well Completed 10/2/02

Plugging Commenced 10/2/02

Plugging Completed 10/2/02

OCT 24 2002

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR SHAKESPEARE OIL Co., Inc.

ADDRESS 202 W. MAIN ST.

PHONE(S) (618) 548-1585 OPERATORS LICENSE NO. 7311

Character of Well D+A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/30/02 (date)

by HERB DINAS, HAYS, KS (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation N/A Depth to Top _____ Bottom _____ T.D. 4728'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0'	235'	8 5/8"	235'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Rotary mud from 4728' to 2550', 2425' to 1500', 1000' to 285', + 85' to 40'.
Cement plugs from 2550' to 2425', 1500' to 1000', 285' to 85', 40' to 0' + 15 sx in the rat hole.
A total of 190 sx 60/40 PMIX, 6% GEL + was placed by drill pipe + cemented by Allied.

Name of Plugging Contractor MURFIN DRILLING Co. RIG #8 License No. 30606

Address 250 N. WATER, SUITE 300 WICHITA, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: SHAKESPEARE OIL Co., Inc.

STATE OF ILLINOIS COUNTY OF MARION, ss.

DONALD R. WILLIAMS, VICE PRESIDENT (Employee of Operator) or (Operator) o
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above-described well as filed the
the same are true and correct, so help me God.

(Signature) Donald R. Williams, V.P.

(Address) 202 W. MAIN ST., SALEM, IL 62881

SUBSCRIBED AND SWORN TO before me this 21ST day of OCTOBER, 2002

Ann M. Smith

Notary Public

My Commission Expires: 11-23-06



OR