


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Logan County, Sec. 36 Twp. 15S Rge. 34W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE NW  
Lease Owner Beren Corporation  
Lease Name McDaniel Well No. 1  
Office Address 970 Fourth Financial Center, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed August 12, 19 75  
Application for plugging filed August 12, 19 75  
Application for plugging approved August 12, 19 75  
Plugging commenced August 12, 19 75  
Plugging completed August 12, 19 75  
Reason for abandonment of well or producing formation D & A



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W.L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4670' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	340'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug #1 @ 1300' w/70 sx. cmt.  
Plug #2 @ 300' w/20 sx. cmt.  
Plug #3 @ 40' w/10 sx. cmt. & 1 sk. hulls  
Cmt. was 50-50 pozmix, 6% gel.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 6 1975

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Red Tiger Drilling Company  
Address 1720 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Linda H. Dickens (employee of owner) or (XXXXXX) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Linda H. Dickens  
1720 Wichita Plaza, Wichita, Kansas 67202  
(Address)

Subscribed and sworn to before me this 15th day of August, 19 75



December 28, 1977

D'Ann Brennan  
Notary Public.

DRILLERS LOG

No. 1 McDaniel

**CASING RECORD:**

8-5/8" @ 340'  
w/200 sx. cmt.

**COMPANY:**

Baren Corporation

**DESCRIPTION:**

C NE NW  
36-155-34W  
Logan County,  
Kansas

**CONTRACTOR:**

Red Tiger Drilling Company

**COMMENCED:**

July 19, 1975

**COMPLETED:**

August 12, 1975

**TOTAL DEPTH: 4670'**

**ELEVATION: 2916' K.B.**

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay & Shale	0	345	
Shale	345	1510	
Shale & Post Rock	1510	1581	
Shallow Anhydrite	1581	1615	
Shale & Clay	1615	1880	
Shale	1880	2295	
Shells	2295	2325	
Shale & Shells	2325	2500	
Shale	2500	2890	
Shale & Lime	2890	3222	
Lime	3222	3295	
Lime & Shale	3295	3579	
Lime	3579	3650	
Lime & Shale	3650	3815	
Lime	3815	4670	

RECEIVED  
STATE GEOLOGICAL COMMISSION

OCT 6 1975

CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens  
Linda H. Dickens

Subscribed and sworn to before me this 15th day of August, 1975.

D'Ann Drennan  
Notary Public

My Commission Expires:

December 28, 1977

