

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-109-20,321-0000

LEASE NAME McDaniel

WELL NUMBER B-1
 140' NW of C NW SE
 SPOT LOCATION _____

SEC. 28 TWP. 15 SRGE. 34 (E) or (W)

COUNTY Logan

Date Well Completed _____

Plugging Commenced 7-30-84

Plugging Completed 8-6-84

LEASE OPERATOR F & M Oil Company

ADDRESS 422 Union Center Wichita, Kansas 67202

PHONE # (316) 262-2636 OPERATORS LICENSE NO. 5313

Character of Well OIL
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4740

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8	391'	none
				4-1/2"	4727'	3541'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped bottom with 40 sacks cement to 3800'. Shot casing @3541', pulled a total of 3541' (86 Joints) of 4-1/2" casing. Plugged surface with 3 hulls, 28 gel, 100 cement, 12 gel, released plug and displaced with 70 sacks cement, 50/50pos, 6% gel, 3%.

Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
 Address Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 27 1984
 08-27-84
 CONSERVATION DIVISION
 Wichita, Kansas

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 23 day of August, 1984

IRENE HOOVER
 State of Kansas
 My Comm. Exp. Aug. 15, 1985

[Signature]
 Notary Public

My Commission expires: _____