


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Logan County, Sec. 35 Twp. 13 Rge. (E) 33(W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner D. R. Lauck Oil Company, Inc.
Lease Name Briggs Ranch Well No. 1
Office Address 301 South Broadway Wichita 2 Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed May 30 19 52
Application for plugging filed May 31 19 52
Application for plugging approved May 31 19 52
Plugging commenced May 31 19 52
Plugging completed May 31 19 52
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4688 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
shale shells		0	211	8 5/8	211	cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

mud 4688 - 1570
10 sax cement 1570 - 1550

To complete the well as a water well, a waiver of responsibility for the plugging of the well was made by Paul Briggs to the D. R. Lauck Oil Company, Inc.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.
James F. Ralstin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James F. Ralstin
Wichita Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of June, 19 52
My commission expires Sept. 14, 1955



RECEIVED
STATE CORPORATION COMMISSION
JUN 4 - 1952
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE - SEC 35 T 13 R 33
BOOK PAGE 21 LINE 14

D. R. Lauck Oil Company, Inc. et.al

Briggs Ranch #1
NE NE NE 35-13-33W. Logan County, Kansas

Commenced May 12, 1952
Completed May 30, 1952

TD 4688 D & A
8 5/8" csg at 211 ft. cemented with 125 sacks
Elevation: 2932 DF 2934 Kelly bushing
all measurements taken from Kelly bushing

shale	80		
shale & shells	645		
shale-shells & sand	680		
shale-lime & shells	1230		
sand & shale	1400	Heebner	3854
shale & shells	1810	Lansing	3898
Anhydrite	1845	base Kansas City	4236
red shale & shells	2065	Marmaton	4253
shale & lime	2215	Cherokee	4385
red bed-shale	2385	Pre-Des Moines	4472
lime	2405	sand	4548-4561
shale & sand	2450	Mississippi	4561
shale & lime	2885	T D	4688
broken lime	2975		
shale & lime	3245	DST #1	3899-3925 open 1 hr.
lime & shale	3295		rec. 2520' salt water
shale & lime	3495		BHP 1180#
lime & shale	3730		
broken lime	3795		IFP 560#
lime	3870		FFP 1160#
broken lime	3893		
lime	4688	DST #2	3861-3892 open 1 hr
			rec. 110 ft drilling mud
			BHP 600#

I hereby certify that the above is a true and correct log of the Briggs Ranch #1 well, to the best of my knowledge and belief. Dated at Wichita, Kansas, this 3rd day of June, 1952.

James F. Ralstin
James F. Ralstin

Subscribed and sworn to before me this 3rd day of June, 1952.

Elizabeth Gay
Notary Public VED
OIL CORPORATION COMMISSION

My commission expires Sept. 14, 1955



PLUGGING
FILE SEC 35T 13R 23W
BOOK PAGE 01 LINE 4

JUN 4 - 1952
OBSERVATION DIVISION
Wichita, Kansas