



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

November 16, 1971

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Julius Ehrlich of Ehrlich Drilling Company has this date requested permission to plug the following described well:

Mr. Ehrlich guarantees payment of the plugging fee.

Operator's full Name: Tom Ehrlich and Jim Ehrlich

Complete Address: Wilson, Kansas 67490

Lease Name: Adolph Vopat Well No. 1

Location: NE NE SW Sec. 19 Twp. 14 Rge. 9 (E)(W) X

County: Ellsworth Total Depth 3160' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ehrlich was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/2 sack hulls to 200' and
cement hole with 35 sacks cement through drill pipe at 200'. Fill
hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole
with 10 sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

[Signature]
Conservation Division Agent