

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-109-20,368-00-00 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Petex, Inc. OPERATORS LICENSE NO. 8541

ADDRESS Route #2, Box 553, Rogersville, MO 65742 PHONE # (417) 887-6289

LEASE (FARM) AHRENS WELL NO. 1 WELL LOCATION C W/2 NW/4 COUNTY Logan

SEC. 21 TWP. 12S RGE. 33W (E) or (W) TOTAL DEPTH 4770' PLUG BACK TO

Check One:

OIL WELL GAS WELL D & A XX SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8" SET AT 304' CEMENTED WITH 230 SACKS

CASING SIZE - - SET AT - - CEMENTED WITH - - SACKS

PERFORATED AT - - - -

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1st plug @ 2640' w/25 sx. 2nd plug @ 1610' w/100 sx. 1 sx. Celoflack. 3rd plug @ 340' w/40 sx. 4th plug @ 40' Sol. Bridge w/10 sx. 10 sx. in Rathole. 10 sx. in Mousehole. 50-50 poz., 6% gel.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? NO
(If not, explain)

Sent to operator for completion.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 12:30 p.m., 1/20/85.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et ~~REGULATIONS OF THE STATE CORPORATION COMMISSION~~ **RECEIVED**

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: **FEB 01 1985**

W.W. Towns (Toolpusher) PHONE # (913) 462-2123 **CONSERVATION DIVISION**
Wichita, Kansas

ADDRESS R.R. #2, Box 1159, Colby, KS 67701

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 801 Union Center, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack L. Partridge
(Operator or Agent)
Jack L. Partridge, Vice Pres.

DATE: January 22, 1985