

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 3017 N. Cypress, Wichita, KS 67226-4003

PHONE# (316) 636-2737 OPERATORS LICENSE NO. 5003

Date Well Completed 7-29-95

Character of Well D&A

Plugging Commenced 7-29-95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-29-95

The plugging proposal was approved on 7-29-95 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4850'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	355	8-5/8"	355	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Plugged and abandoned using 60/40 Pozmix, 6%gel. Set 1st plug @ 2160' w/50 sx; 2nd plug set @ 1250' w/80 sx; 3rd plug set @ 390' w/50 sx; 4th plug set @ 40' w/10 sx; 15 sx in rathole and 10 sx in mousehole. Plugging complete 5:35 a.m. 7-29-95

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sweetman Drilling, Inc. License No. 5658

Address 3017 N. Cypress, Wichita, KS 67226-4003

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


McCoy Petroleum Corporation (~~Employee of Operator~~) RECEIVED (~~Operator~~) c

above-described well, being first duly sworn on oath, says: That I have known the contents of the above statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature] AUG 17 1995

(Address) 3017 N. Cypress  
Wichita, KS 67226-4003

SUBSCRIBED AND SWORN TO before me this 1st day of August, 19 95



Deborah Ann Paulus  
Notary Public

January 8, 1996

FOR KCC USE:

FORM C-1 7/9

FORM MUST BE TYPE

FORM MUST BE SIGNE

EFFECTIVE DATE: 6-14-95

State of Kansas 171-20,489-0000

ALL BLANKS MUST BE FILLED SGA? Yes  No  Must be approved by the K.C.

NOTICE OF INTENTION TO DRILL DIST # 1

five (5) days prior to commencing well

Expected Spud Date 7 1 1995  
month day year

Spot NE SE Sec 11 Twp 20 S. Rg 33 East  
E/2 West

OPERATOR: License # 5003  
Name: McCoy Petroleum Corporation  
Address: 3017 N. Cypress  
City/State/Zip: Wichita, KS 67226-4003  
Contact Person: Tim Pierce  
Phone: (316) 636-2737

1981 feet f. South / North line of Section:  
330 feet from East / West line of Section:  
IS SECTION X REGULAR  IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side  
County: Scott

Lease Name: Wasinger "B" Well #: 1-11

Field Name: Shallow Water NE

Is this a Prorated/Spaced Field? yes  no

Target Formation(s): Lansing/MRW/Miss

Nearest lease or unit boundary: 330'

Ground Surface Elevation: 2945 feet MSL

Water well within one-quarter mile:  yes  no

Public water supply well within one mile:  yes  no

Depth to bottom of fresh water: 180'

Depth to bottom of usable water: 1200'

Surface Pipe by Alternate: 1  2

Length of Surface Pipe Planned to be set: 350'

Length of Conductor pipe required: 0

Projected Total Depth: 4800'

Formation at Total Depth: Mississippi

Water Source for Drilling Operations:  
 well  farm pond  other

DWR Permit #: Existing irrigation well

Will Cores Be Taken?:  yes  no

If yes, proposed zone: \_\_\_\_\_

CONTRACTOR: License # 5658  
Name: Sweetman Drilling, Inc.

Well Drilled For: Well Class: Type Equipment:  
 Oil ... Enh Rec ... Infield  Mud Rotary  
 Gas ... Storage  Pool Ext. ... Air Rotary  
... OVVQ ... Disposal ... Wildcat ... Cable  
... Seismic: ... # of Holes ... Other  
... Other \_\_\_\_\_

If OVVQ: old well information as follows:

Operator: \_\_\_\_\_

Well Name: \_\_\_\_\_

Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal wellbore?  yes  no

If yes, true vertical depth: \_\_\_\_\_

Bottom Hole Location: \_\_\_\_\_

Exp. 12/9/95

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well comply with K.S.A. 55

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 07 1995

Pusher Engatic Soloye INIT. R.C.  
SPUD DATE 7-19-95  
LENGTH SURFACE PLANNED 350  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 3/4 @ 355 CONDUCTOR  
ANHYDRITE T- 2100 B- 2170 ELEVATION  
TD 4850 FORMATION \_\_\_\_\_  
RAN PIPE @ \_\_\_\_\_ DV TOOL \_\_\_\_\_ ALT II DONE \_\_\_\_\_  
Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX \_\_\_\_\_  
Hug./Council @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX \_\_\_\_\_  
Anhydrite Base @ 2160 Ft. W/ 50 SX ✓  
1/2 Base Anyh. @ 1250 Ft. W/ 80 SX ✓  
1/2, 1/2 Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX \_\_\_\_\_  
Bottom Surface @ 390 Ft. W/ 50 SX ✓  
40' Plug @ 40 Ft. W/ 10 SX ✓  
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX ✓  
WATER WELL \_\_\_\_\_ SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_  
Hauling \_\_\_\_\_  
TECHNICIAN B.W.L. DATE 7-27-95  
TYPE OF CEMENT 60/40 per 60/60 1/4 F/1054  
STARTING TIME \_\_\_\_\_ (AM/PM) DATE \_\_\_\_\_  
COMPLETION TIME 5:35 (AM/PM) DATE 7-29  
CEMENT COMPANY Allred