

Give All Information Completely
Make Required Affidavit - Mail
Or Deliver Report To:

Scott County, Sec. 11 Twp. 20S Rge. 33 E/W
Location As "NE/CNW 1/4 SW1/4" Or Footage From Lines
SE NE NE

Conversation Division
State Corporation Commission
200 Colorado Derby Building
Wichita, Kansas 67202

Lease Owner C. L. Morris Co.

Lease Name Wasinger Well No. #1

Office Address P.O. Box 204 Wichita, Ks. 67202

Character Of Well (Completed As Oil, Gas Or Dry Hole) _____

Dry Hole

Date Well Completed 7-4 19 81

Application For Plugging Filed 7-4 19 81

Application For Plugging Approved 7-4 19 81

Plugging Commenced 7-4 19 81

Plugging Completed 7-4 19 81

Reason For Abandonment Of Well Or Producing Formation _____

Dry Hole

If A Producing Well Is Abandoned, Date Of Last Production _____

19

Was Permission Obtained From The Conservation Division Or
Its Agents Before Plugging Was Commenced? Yes

Name Of Conservation Agent Who Supervised Plugging Of This Well Marion Schmidt

Producing Formation _____ Depth To Top _____ Bottom _____ Total Depth Of Well 4661'

Show Depth And Thickness Of All Water, Oil And Gas Formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	336'	None

Describe In Detail The Manner In Which The Well Was Plugged, Indicating Where The Mud Fluid Was
Placed And The Method Or Methods Used In Introducing It Into The Hole. If Cement Or Other Plugs
Were Used, State The Character Of Same And Depth Placed, From _____ Feet To _____ Feet
For Each Plug Set. 1st @ 1130' w/60 sx 50-50 poz, 6% gel

2st @ 330' w/ 30 sx 50-50 poz, 6% gel

3st @ 40' w/ 10 sx 50-50 poz, 6% gel.

5 sx in rat hole

RECEIVED
STATE CORPORATION COMMISSION
7-28-81
JUL 28 1981

Please Note: (If Additional Description If Necessary, Use Bank Of This Sheet)

Name Of Plugging Contractor RAMCO DRILLING CO.

State Of Kansas County Of Sedgwick ss: J. V. Crawford


~~of RAMCO DRILLING CO.~~ ~~of the above described~~

~~RAMCO~~ being first duly sworn on oath, says: That I have knowledge of the facts, statements and
matters herein contained and the log of the above described well as filed and that same are true
and correct. So help me God.

THE RAMCO DRILLING CORPORATION

Signature: [Signature]
(Address)

Subscribed And Sworn To Before Me This 23 Day Of July, 19 81



[Signature]
Notary Public

My Commission Expires: 6-5-84

W E L L L O G

15-171-20211-0000

WELL NAME: Wasinger #1

OPERATOR: C. L. Morris Co.

SPUD DATE: 6-26-81

CONTRACTOR: Ramco Drilling Co.

COMPLETION DATE: 7-4-81

CASING: 20# 8 5/8" @ 336' w/200 sx
60/40 poz, 3% cc.

LOCATION: SE NE NE 11-20S-33W

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface and Clay	0	343
Shale and shells	343	1381
Shale	1381	1855
Shale and Sand	1855	2140
Sand	2140	2473
Shale and Sand	2473	2608
Lime	2608	3078
Lime and Shale	3078	3225
Shale and Lime	3225	3568
Lime and Shale	3568	3763
Shale and Lime	3763	3939
Lime and Shale	3939	4550
Shale	4550	4661
RTD	4661	

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1981

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS


COUNTY OF SEDGWICK

I certify that the above information is true and correct to the best of my knowledge.

THE RAMCO DRILLING-CORPORATION

By: *[Signature]*

Subscribed and sworn to before me on this 23 day of July, 1981.



Sandra Kay May
Notary Public

My Appointment Expires: 6-5-84