


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines Scott County. Sec. 9 Twp. 20 Rge. 33 (E) (W) X  
Location as "NE/CNW/SW" or footage from lines C NE/4  
Lease Owner Shallow Water Refining Company  
Lease Name Hamilton Well No. #1  
Office Address 542 Petroleum Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved 7-25-62 19\_\_\_\_  
Plugging commenced 9-8-62 19\_\_\_\_  
Plugging completed 9-13-62 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2700' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded off bottom - mixed and dumped 5 sacks cement.  
Mudded hole to 200' - mixed and dumped 35 sacks cement.  
Mudded hole to 45' mixed and dumped 15 sacks cement for top cap.

**RECEIVED**  
STATE CORPORATION COMMISSION

SEP 18 1962  
9-18-62  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.  
Address Box 364, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.


Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.  
Box 364, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 17 day of Sept., 1962

My commission expires 24 October 1964

Sidney D. Miller  
Notary Public.



THE SHALLOW WATER REFINING COMPANY - Operator  
SIFRA PETROLEUM CO., INC. - Contractor

T. D.: 2700'

HAMILTON #1  
C NE 1/4  
Sec. 9-20S-33W  
Scott County, Kansas

Commenced: 5-17-62  
Completed: 5-22-62

Casing:

8-5/8" Set at 222'  
4-1/2" Set at 2699'

Cement:

with 175 sx. cement  
with 125 sx. cement

FORMATION

DEPTH

Surface Soil & Clay	30
Sand	180
Shale	222
Sand & Shale	710
Shale & Shells	1345
Red Bed & Shale	1485
Sand & Shale	1550
Red Bed & Shale	2340
Shale & Shells	2448
Lime & Shale	2573
Lime, Shale & Anhydrite	2609
Lime	2663
Broken Lime	2700

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 26 1962  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          ) ss:  
COUNTY OF RUSSELL )

I hereby certify that the above information is true  
and correct to the best of my knowledge.

C. T. Honaker

Subscribed and sworn to before me this day (24th) of May,  
1962.

Leroy Dietz  
Notary Public

My commission expires; 10-17-63

