

TATE OF KANSAS
 TATE CORPORATION COMMISSION
 30 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-02-3-117

API NUMBER 15-171-20,277 00-0

LEASE NAME LANG

WELL NUMBER 1-6

550 Ft. from S Section Line

600 Ft. from E Section Line

SEC. 6 TWP. 20S RGE. 33W (E) or (W)

COUNTY Scott

Date Well Completed _____

Plugging Commenced 2-26-01

Plugging Completed 3-1-01

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR LEBSACK OIL PRODUCTIONS, INC.

ADDRESS P.O. Box 489 Hays, Kansas 67601

PHONE (785) 625-5444 OPERATORS LICENSE NO. 5210

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 4794'

Show depth and thickness of all water, oil and gas formations.

STATE CORPORATION COMMISSION

3-20-01
MAR 20 2001

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	425'	None
				5-1/2"	4788'	1610'

CONSERVATION DIVISION
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each section.
Plugged off bottom with sand to 4600' and 5 sks. cement. Shot pipe @2200' and 1610'.
Pulled up to 1250', pumped 80 sks. cement and 14 sks. gel, pulled up to 460', pumped
50 sks. cement, pulled up to 40' and pumped 10 sks. cement. 60/40 pos. 6% gel.
 Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lebsack Oil Production, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
 above-described well, being first duly sworn on oath, says: That I have knowledge of the fact
 statements, and matters herein contained and the log of the above-described well as filed to
 the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 16th day of February, 2001.

[Signature]
 Notary Public

My Commission Expires: _____



Form CP
 Revised 05-

oe