


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-167-00481-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Russell County, Sec. 8 Twp. 14 Rge. 12 (E) (W) X
Location as "NE/CNW/SW" or footage from lines C SW SW
Lease Owner Messman & Rinehart Oil Co.
Lease Name Mahoney Well No. #1
Office Address 518 Petroleum Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 1-9-62 19____
Plugging completed 1-13-62 19____
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2170 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 2300'. Mixed and ran 1/2 sacks cement thru dump bailer.
Pulled pipe.
Mudded hole to 250' and sat 10' rock bridge. Mixed and ran 25 sacks cement thru dump bailer. Mudded hole to 40' and sat 10' rock bridge. Mixed and dumped 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JAN 1 1962
CONSERVATION DIVISION
Wichita, Kansas
01-15-1962

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 13 day of January, 1962
Erney D. Miller
Notary Public.



15-167-00481-00-00

NO. 1 HANNEY

Well Log:

Location:	App. Ctr. SW/4 SW/4 Section 8-14S-12W Russell County, Kansas	Commenced:	April 20, 1960
Operator:	Messman-Rinehart Oil Company 518 Petroleum Building Wichita, Kansas	Completed:	April 27, 1960 (Rotary)
Contractor:	Messman-Rinehart Oil Company 518 Petroleum Building Wichita, Kansas	Elevation:	1809' K/S
Casing Record:	8-5/8" @ 254' w/125 sq. con., 2 gal., 2 c.c. 4-1/2" @ 2470' w/60 sq. con., 1 gal.	Production:	Gas

*** LOG ***

Clay & Rock	40
Clay & shale	254
Red Bed & Clay	723
Anhydrite	760
Red Bed, shale & shells	900
Shale & shells	1400
Lime & shale	2100
Shale	2425
Sand & shale	2436
Shale	2505
Sand & shale	2536 R.T.D.

Sample Tops:

728 - Anhydrite (#1081)
2368 - Tarkio Lime (-559)

The undersigned, MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

MESSMAN-RINEHART OIL COMPANY

By: _____

J. A. Gilliland
J. A. Gilliland

Subscribed and sworn to before me this 27th day of July, 1960.

Barbara J. Scott
Barbara J. Scott, Notary Public

My Commission Expires: December 1, 1960

RECEIVED
STATE CORPORATION COMMISSION

FEB 5 1962
02-05-1962
CONSERVATION DIVISION
Wichita, Kansas



COMPLETION DATA

Hessman-Rinehart Oil Company
No. 1 Mahoney
App. Ctr. SW/4 SW/4
Section 8-143-121
Russell County, Kansas

- 5/13/60 -- Moved in cable tools
Perf. 2304-10' w/4⁵ ft., Treated w/250 gal. mud acid,
Ga. 50,000 cfg (estl.)
Treated w/500 gal. mud acid, decreased to good show gas
Perf. 2414-20' w/4⁵, Ga. 2,250,000 cfg. natural, Tbg. 700#
Csg. 700# (bldg.), no water
- 5/15/60 -- Shut in awaiting connection

HESSMAN-RINEHART OIL COMPANY

By: Roger L. Hessman
Roger L. Hessman

RLW/bjs
7/27/60

RECEIVED
CORPORATION COMMISSION
FEB 5 1962
CONSERVATION DIVISION
Wichita, Kansas