

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

Form CP-4 March 2009

Type or Print on this Form Form must be Signed All blanks must be Filled

WELL PLUGGING RECORD K.A.R. 82-3-117

OPERATOR: License #: 30458 Name: RJM Oil Company, Inc. Address 1: PO Box 256 Address 2: City: Claflin State: KS Zip: 67525 Contact Person: Chris Hoffman Phone: (620) 786-8744 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API No. 15 - 009-25597-00-00 Spot Description: NW NE NW SE NW Sec. 5 Twp. 19 S. R. 14 East West 1,450 Feet from North / South Line of Section 1,600 Feet from East / West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Barton Lease Name: Nordman Well #: 1 Date Well Completed: 8/9/2011 The plugging proposal was approved on: 8/8/2011 (Date) by: Darryle (KCC District Agent's Name) Plugging Commenced: 8/9/2011 Plugging Completed: 8/9/2011

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: Surface, 8 5/8", 861', 0'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well with 185 sacks of 60/40 Poz, 4% gel, 1/4# flo-seal per sack, 1st plug @ 3505' with 25 sacks, 2nd plug @ 925' with 40 sacks, 3rd plug @ 425' with 80 sacks, 4th plug @ 40' to surface with 10 sacks, 30 sacks for rat hole, by Quality (Ticket #5069), plug was down @ 1:00 pm on 8/9/2011.

RECEIVED

AUG 11 2011

KCC WICHITA

Plugging Contractor License #: 33350 Name: Southwind Drilling, Inc. Address 1: PO Box 276 Address 2: City: Ellinwood State: Kansas Zip: 67526 Phone: (620) 564-3800

Name of Party Responsible for Plugging Fees: RJM Oil Company, Inc. State of Kansas County: Barton, ss. Jennifer Heape (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jennifer Heape



Southwind Drilling, Inc.
Plugging Orders & Reports

Lease: Nordman #1

Plugging Received from KCC Representative:

Name: Darryle Date: 8-8-11 Time: 1:08 PM

1st plug @ 350.5 feet, 25 sacks Stands 57

~~2nd plug @ 92.5 feet, 40 sacks Stands 14 1/2~~

3rd plug @ 425 feet, 80 sacks Stands 6 1/2

4th plug @ 40 feet, 10 sacks Stands 1 JT

5th plug @ _____ feet, _____ sacks Stands _____

Mousehole: _____ sacks

Rathole: 30 sacks

Total Cement Used: 185 sacks

Type of cement: 60/40 P02 4% Gel 1/4" Floseal

Plug Down @ 1:00 PM 8-9-11

Call KCC When Completed: _____

Name: PaT Date: 8-9-11 Time: 1:35 PM

RECEIVED
AUG 11 2011
KCC WICHITA