

1 030470

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,264-0000

W/2 SW NW, SEC. 25, T 20 S, R 34 (W) X

3300 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5469

Lease Name Crist "C" Well # 1

Operator: Anadarko Production Company

County Scott 162.50

Name & Address P. O. Box 351

Well Total Depth 5000 feet

Liberal, KS 67901

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 1175'

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address P. O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 4:00 pm Day: 3 Month: June Year: 19 85

Plugging proposal received from Doug Blair

(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 4915' PBD 4849' Perfs at 4714-18' Pump through 4 1/2" with mud between plugs

1st plug pump 2 sx hulls and 50 sx cement to bottom

2nd plug - pull to 1275' and pump 50 sx cement

3rd plug - pull to 1125' and pump 50 sx cement

4th plug - pull to 450' and pump 25 sx cement solid bridge

5th plug hulls - plug at 40' Plugging Proposal Received by Steve Durrant (TECHNICIAN) cement to surface with 10 sx cement.

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:00 pm Day: 3 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 50 sx cement and 2 sx hulls from 4718-4300',

2nd plug pumped 50 sx cement at 1225', 3rd plug pumped 25 sx cement at 450', 4th & 5th

plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement

Recovered 1730' 4 1/2" casing. Used Common Cement by Sargent's

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

1 Agent did not observe this plugging.

DATE 9/1/1985

INV. NO. 9246

6-3

AUG 06 1985

JUL 26 1985

7-26-85

CONSERVATION DIVISION
Wichita, Kansas

Signed Steve Durrant (TECHNICIAN)