

To: 1 020698
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-26 API NUMBER 15- 171-30066-0000 Drill Completion Date 6/5/66

402NE NW, SEC. 32, T. 20 S, R. 34 W/E
4620 feet from S section line
3300 feet from E section line
Lease Name Crist B Well # 1
County Scott 165.75
Well Total Depth 5100 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 465

TECHNICIAN'S PLUGGING REPORT
Operator License # 5848
Operator: Herman Lang Oil & Gas
Name & Address 70 N. Farmland Rd.
Garden City, KS 67846

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 25 Month: 8 Year: 19 93

Plugging proposal received from Doug Blair
(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 4700' w/175 sx cement, PBDT 4664', Perfs at 4556-62, 4574-80'
1st plug set CIBP at 4215' with 2 sx cement on top, load hole with=mud,
2nd plug perforate pipe at 1190' and 1127', pump 75 sx cement, displace down to 1000',
3rd plug pump 50 'sx cement at 500',
4th plug pump 10 sx cement at 40',

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____
Operations Completed: Hour: 4 p.m. Day: 26 Month: 8 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4215' with 2 sx cement on top, loaded hole with mud
2nd plug perforated pipe at 1190' & 1127', pumped 75 sx cement, displaced down to 1000',
3rd plug pumped 50 sx cement at 500',
4th plug pumped 10 sx cement at 40 to -4'.

Remarks: Used common cement by Sargent's. Recovered 785' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did, ~~did not~~) observe this plugging.

DATE 9-9-93

INV. NO. 38573

8-26

Signed Glenn R. Barlow (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
8-31-93
AUG 31 1993
CONSERVATION DIVISION
Wichita, Kansas