

1 051061

6-7-88

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-171-20,371-0000

C. NE. NE, SEC. 35, T. 20 S, R. 34 W/E

4620 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Crist Well # 1-35

Operator: Gear Petroleum Company, Inc.

County Scott 160.03

Name: Gear Petroleum Company, Inc.

Well Total Depth 4924 feet

Address 1075 Kansas State Bank Bldg.

Conductor Pipe: Size _____ feet

125 North Market.

Surface Casing: Size 8 5/8 feet 412

Wichita, KS 67202

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Bldg., Wichita, KS 67202

Company to plug at: Hour: 4:20 a.m. Day: 7 Month: 6 Year: 19 88

Plugging proposal received from Mike Waggoner

(company name) Red Tiger Drilling Company (phone) 316-263-1201

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2142'
1st plug at 2160' with 50 sx cement, 2nd plug at 1400' with 80 sx cement,
3rd plug at 430' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:30 a.m. Day: 7 Month: RECEIVED Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 2160' with 50 sx cement STATE CORPORATION COMMISSION

2nd plug at 1400' with 80 sx cement,

3rd plug at 430' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

JUN - 8 1988
6-8-88

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

~~XXXX~~ / did not observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED

DATE 6-29-88

INV. NO. 21115