

1 030383

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,248-0000  
SE NE NW , SEC. 20 , T 20 S, R 34 W/E  
4290 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393  
Operator: A. L. Abercrombie  
Name & Address 801 Union Center  
Wichita, KS 67202

Lease Name Minnix Well # 1  
County Scott 164.13  
Well Total Depth 5050 feet  
Conductor Pipe: Size \_\_\_\_\_ feet ✓  
Surface Casing: Size 8 5/8 feet 481

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 6:00 pm Day: 13 Month: March Year: 19 85

Plugging proposal received from Ron Hoover  
(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 5048' PBDT 4550 Perfs at 4496-4500' 4520-23' 4530-453'

1st plug sand back to 4450' and dump 4 sx cement on top of sand through bailer  
2nd plug squeeze well with 3 sx hulls, 15 sx gel, 75 sx cement, 15 sx gel, 1 sack hulls,  
release 8 5/8" rubber plug and pump 175 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 7:45 pm Day: 13 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4450' and dumped 4 sx cement on top of  
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 75 sx cement,  
15 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 175 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 15 1985  
3-15-85  
CONSERVATION DIVISION  
Wichita, Kansas

Maximum pressure 500 psi and shut in 50 psi  
Remarks: Recovered 3002' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% Vee  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-18-85

INV NO. 7353

Signed Steve Durrant SQ  
(TECHNICIAN)