

To: 1 030829
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,358-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5210

Operator: Lebsack Oil Production, Inc.
Name & Address P.O. Box 489
Hays, KS 67601

N/2 NW NW, SEC. 6, T. 20 S, R. 32 W/E
4950 feet from S section line
4620 feet from E section line

Lease Name Stucky Well # 1-6

County Scott 155.03

Well Total Depth 4770 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 372

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 2 a.m. Day: 15 Month: 7 Year: 19 87

Plugging proposal received from Wayne Shively

(company name) Abercrombie Drilling (phone) 913-743-6308

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2930'
Anhydrite 2170-86'

1st plug at 2180' with 50 sx cement, 2nd plug at 1450' with 80 sx cement,

3rd plug at 390' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:30 a. Day: 15 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2180' with 50 sx cement,

2nd plug at 1450' with 80 sx cement,

3rd plug at 390' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If you did not observe this plugging.)

DATE 7-21-87

INV. NO. 17532

Signed Steve Durrant
(TECHNICIAN)

JUL 16 1987
7-16-87
CONSERVATION DIVISION
Wichita, Kansas

7-15 SEP 17 1987