

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-21650-00-00
Spot: NWNWSENE Sec/Twnshp/Rge: 10-22S-36W
3953 feet from S Section Line, 1264 feet from E Section Line
Lease Name: WIGGINS Well #: 1-10
County: KEARNY Total Vertical Depth: 2770 feet

Operator License No.: 9152
Op Name: MAREXCO, INC.
Address: 3033 NW 63RD ST - STE 151
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	317		WITH 200 SX CMT
T1	2.375	2725		
PROD	4.5	2770	0	WITH 575 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/13/2011 2:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LLOYD WILLIAMS Company: MAREXCO Phone: (405) 286-5657

Proposed Plugging Method: PUMP 300# HULLS & 40 SX CMT. DISPLACED TO 2100'. PUMP CMT FROM 900' & CIRCULATE THROUGH TBG.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/13/2011 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG PUMP 40 SX CMT WITH 250# HULLS TO 2720'. DISPLACE TO 2720'. HOLDING AT 450#. 2ND PLUG RUN TBG TO 992' & CIRCULATE 4 1/2" CASING FULL OF CMT TO 0' WITH 120 SX CMT. 3RD PLUG TOO H WITH TBG. TOP OFF 4 1/2" CASING WITH 10 SX CMT. 4TH PLUG PUMP 35 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS TO 200# & HELD.

Perfs:

Top	Bot	Thru	Comments
2717	2720		
2708	2713		
2681	2701		


RECEIVED
AUG 08 2011
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED

JUL 28 2011

KCC DODGE CITY

Form 08-13