

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23729-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 21-8S-21W  
950 feet from N Section Line, 900 feet from W Section Line  
Lease Name: KENYON Well #: 1  
County: GRAHAM Total Vertical Depth: 3703 feet

Operator License No.: 33491  
Op Name: KING, RODNEY L. DBA KING OIL OPER  
Address: 696 D FAIRGROUND RD  
ELLIS, KS 67637

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	224		150 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/11/2011 9:45 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: KING OIL OPERATION Phone: (785) 726-3498

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS Witness Type: NONE  
Date/Time Plugging Completed: 04/11/2011 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st. Plug at 3646' w/25 sxs.  
2nd. Plug at 1655' w/25 sxs.  
3rd. Plug at 885' w/100 sxs.  
4th. Plug at 275' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.

Perfs:


Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

RECEIVED  
AUG 08 2011  
KCC WICHITA

District: 04

Signed

  
(TECHNICIAN)

CM

Form CP-2/3

AUG 04 2011