

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-20615-00-00  
Spot: S2SE Sec/Twnshp/Rge: 17-4S-19W  
660 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: VANKOOTEN Well #: 1  
County: PHILLIPS Total Vertical Depth: 3437 feet

Operator License No.: 31569  
Op Name: BACH, JASON DBA BACH OIL PRODUC  
Address: PO BOX 723  
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	215	0	150 SX CMT COMMON 3% CC, 2% GEL
T1	2.375	3400		
PROD	5.5	3437	0	550 SX CMT ALHD

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/27/2011 11:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DALE FERLAND Company: BACH OIL PRODUCTION Phone: (785) 302-1435

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 500# hulls - 12 sxs gel spacer.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/27/2011 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing - pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls - followed with 12 sxs gel spacer.  
Pumped 190 sxs 60/40 pozmix - 4% gel with 300# hulls.  
S.I.P. 400#.  
Hooked to 8 5/8" x 5 1/2" annulus. Pressured to 300# immediately.

Perfs:

Top	Bot	Thru	Comments
3271	3273		
3255	3257		
3215	3218		
3159	3162		TORONTO

RECEIVED  
AUG 08 2011  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #38126.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

CM

Form CP-2/3

JUL 29 2011