

8/08 ml

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20058-00-00
Spot: NESESW Sec/Twnshp/Rge: 20-4S-19W
990 feet from S Section Line, 2310 feet from W Section Line
Lease Name: REYNOLDS Well #: 1
County: PHILLIPS Total Vertical Depth: 3350 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	190	0	165 sx
PROD	5.5	3339	0	275 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/27/2011 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DALE FERLAND Company: BACH OIL PRODUCTION Phone: (785) 302-1435

Proposed Plugging Method: Ordered 305 sxs 60/40 pozmix - 4% gel - 500# hulls - 12 sxs gel spacer.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/27/2011 11:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3060' - pumped 12 sxs gel spacer - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1400' - pumped 130 sxs 60/40 pozmix - 4% gel with 300# hulls to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing with 30 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 5 1/2" annulus. Pumped 5 sxs 60/40 pozmix - 4% gel.
S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3261	3268		Lansing
3243	3249		Lansing
3224	3230		Lansing
3191	3196		Lansing
3173	3176		Toronto

RECEIVED
AUG 08 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #38125.

Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN)

CM

JUL 29 2011