

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02686-00-00
Spot: NWSESW Sec/Twnshp/Rge: 6-13S-17W
990 feet from S Section Line, 3630 feet from E Section Line
Lease Name: STAAB Well #: 'A' 2
County: ELLIS Total Vertical Depth: 3587 feet

Operator License No.: 5145
Op Name: DREILING OIL INC
Address: 1008 CODY AVE PO BOX 550
HAYS, KS 67601

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 95 | 0 | 100 SX |
| PROD | 5.5 | 3578 | 0 | 150 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/01/2011 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TERRY W. PIESKER Company: DREILING OIL INC. Phone: (785) 625-8327

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.
Well has been squeezed numerous time from 2600' to surface.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/01/2011 1:50 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH to 3212'.
Allied rigged to tubing and mixed and pumped 125 sxs 60/40 pozmix - 4% gel with 300# hulls mixed in.
Pulled tubing to 2012'. Allied rigged to tubing and pumped 235 sxs cement with 200# hulls mixed in to circulate cement to surface.
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 20 sxs cement.
Max. P.S.I. 800# S.I.P. 800#.
Rigged to 8 5/8" casing and pumped 20 sxs cement.
Max. P.S.I. 250#. S.I.P. 250#.

Perfs:


| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3579 | 3587 | | OHIO |
| 3536 | 3540 | | OHIO |
| 3514 | 3517 | | OHIO |
| 3488 | 3490 | | OHIO |
| 3472 | 3475 | | OHIO |
| 3448 | 3452 | | OHIO |
| 3405 | 3411 | | OHIO |
| 3398 | 3402 | | OHIO |
| 3389 | 3392 | | OHIO |
| 3362 | 3366 | | OHIO |
| 3343 | 3348 | | OHIO |

RECEIVED
AUG 0 8 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #38131.

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN)

CM

AUG 0 4 2011