

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02685-00-00
Spot: NENWSW Sec/Twnshp/Rge: 6-13S-17W
2310 feet from S Section Line, 990 feet from W Section Line
Lease Name: STAAB Well #: 'A' 1
County: ELLIS Total Vertical Depth: 3611 feet

Operator License No.: 5145
Op Name: DREILING OIL INC
Address: 1008 CODY AVE PO BOX 550
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	120	0	75 SX CMT
PROD	5.5	3593	0	125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/01/2011 2:30 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TERRY W. PIESKER Company: DREILING OIL INC. Phone: (785) 625-8327

Proposed Plugging Method: Ordered 315 sxs 60/40 pozmix - 4% gel - 500# hulls - 13 sxs gel.
Well has been squeezed 2600' to surface numerous times.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/01/2011 8:05 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 3497'.
Allied rigged to tubing and pumped 13 sxs gel - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in.
Pulled tubing to 1857'. Allied rigged to tubing and pumped 180 sxs cement with 300# hulls mixed in - ran out of cement.
Pulled tubing to 585'. Pumped 75 sxs cement to circulate cement to surface.
Pulled tubing - topped off 5 1/2" casing with 10 sxs cement - 8 5/8" full of cement.

Perfs:

Top	Bot	Thru	Comments
3594	3611		OHIO
3428	3433		
3412	3416		

RECEIVED
AUG 08 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #38132.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

CM