

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-051-01401-00-00
 Spot: NWNENE Sec/Twnshp/Rge: 10-12S-16W
4950 feet from S Section Line, 990 feet from E Section Line
 Lease Name: DICKINSON A Well #: 3
 County: ELLIS Total Vertical Depth: 3413 feet

Operator License No.: 5145
 Op Name: DREILING OIL INC
 Address: 1008 CODY AVE PO BOX 550
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2800		
CIBP		3290		
SURF	8.625	216	0	140 SX
PROD	5.5	3413	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/02/2011 3:00 PM
 Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
 Proposal Rcvd. from: TERRY W. PEISKER Company: DREILING OIL INC. Phone: (785) 625-8327

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.
 CIBP at 3290'. CIBP at 2800'. Covered with cement.
 Squeezed from 2600' to surface - casing leaks.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
 Date/Time Plugging Completed: 08/02/2011 6:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 2760'.
 Allied rigged to tubing and mixed and pumped 115 sxs 60/40 pozmix - 4% gel with 250# hulls mixed in.
 Pulled tubing to 1644'. Allied rigged to tubing and pumped 145 sxs cement with 250# hulls to circulate cement to surface.
 Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 35 sxs cement.
 Max. P.S.I. 500#. S.I.P. 400#.
 Rigged to 8 5/8" casing and pumped 5 sxs cement.
 Max. P.S.I. 250#. S.I.P. 250#.

Perfs:

Top	Bot	Thru	Comments
3372	3377		
3357	3360		
3340	3346		
3262	3264		
3231	3233		
3211	3214		
3184	3186		
3135	3141		
3096	3102		
3079	3082		
2942	2945		
2781	2784		

RECEIVED
 AUG 08 2011
 KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #38134.

Plugged through: TBG

District: 04

Signed _____

(Signature)
 (TECHNICIAN)

CM

AUG 04 2011