

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19151-00-01
Spot: NWNW Sec/Twnshp/Rge: 3-14S-15W
330 feet from N Section Line, 660 feet from W Section Line
Lease Name: FOSTER B Well #: 18
County: RUSSELL Total Vertical Depth: 3303 feet

Operator License No.: 31428
Op Name: CRAWFORD, JEFF DBA LONESTAR OIL
Address: PO BOX 417
VICTORIA, KS 67671

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	922	0	w/unknown sxs cmt
L1	4.5	3298		
PROD	7	3065	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/28/2011 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JEFF CRAWFORD Company: LONESTAR OIL CO Phone: (785) 735-2725

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 800# hulls - 18 sxs gel spacer.
Emergency plug with rig over the hole.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/28/2011 1:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perfed at 1700' and 900'.
Ran tubing to 2943' - pumped 10 sxs gel - 50 sxs cement with 100# hulls.
Pulled to 1878' - pumped 8 sxs gel - 100 sxs cement with 200# hulls.
Pulled to 925' - pumped 75 sxs cement with 200# hulls.
Pulled to 400' - pumped 80 sxs cement - circulated to surface on casing.
Pulled tubing - topped off with 10 sxs cement.
Tied to surface pipe - pressured to 300# P.S.I. - would not take any more cement.

38.87003
98.98174

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

RECEIVED
AUG 08 2011

KCC WICHITA

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

AUG 02 2011