

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-21377-00-00  
Spot: E2SESWNW Sec/Twnshp/Rge: 2-31S-33W  
2970 feet from S Section Line, 4030 feet from E Section Line  
Lease Name: YEAGER Well #: 2-2  
County: SEWARD Total Vertical Depth: 2790 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	629		WITH 330 SX CMT
PROD	4.5	2790	0	WITH 665 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/26/2011 9:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KENNY ANDREWS Company: OXY USA Phone: (620) 629-4232

Proposed Plugging Method: RUN TBG TO 1400' & PUMP 200# HULLS & FILL 4 1/2" CASING WITH CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: NONE  
Date/Time Plugging Completed: 07/27/2011 5:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

\*\*TBG STUCK & PARTED @ 1409'. RODS PARTED AT APP. 1400'. FLUID LEVEL AT 500'. CASING LEAK UNKNOWN.\*\* COULD ONLY GET TBG DOWN TO 1000'. PUMPED 200# HULLS & 30 SX CMT AT 1000'. SDON. 7/27/11: TAGGED TOC @ 920'. PUMPED 70 SX CMT AT 920' & CIRCULATED CMT TO SURFACE. BACKSIDE TOOK 5 SX CMT & PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
2712	2725		WINFIELD
2683	2692		KRIDER
2673	2680		KRIDER
2636	2664		KRIDER
2607	2611		HERRINGTON

RECEIVED  
AUG 08 2011  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: TBG

District: 01

Signed

*Jack MacLasky*  
(TECHNICIAN)

RECEIVED

JUL 29 2011

KCC DODGE CITY

FORM CP-273