

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20012-00-00  
Spot: S2N2NENW Sec/Twnshp/Rge: 2-29S-34W  
4728 feet from S Section Line, 3291 feet from E Section Line  
Lease Name: ONION B Well #: 1  
County: HASKELL Total Vertical Depth: 4800 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1821		WITH 800 SX CMT
DVT		2758		
PROD	5.5	4750	1993	WITH 400 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/20/2011 9:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CHECK BOTTOM. RUN TBG TO BOTTOM OR CIB AT 4600'. CIBP @ 4075'. PLUG AT 1850' OR 1500' WITH 50 SX CMT. PLUG AT 680' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/20/2011 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TAGGED FILL UP AT 3954'. 1ST PLUG PUMP 40 SX CMT THROUGH TBG AT 3954'.  
2ND PLUG AT 1850' WITH 50 SX CMT. 3RD PLUG AT 680' WITH 40 SX CMT. 4TH  
PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4685	4690		MARMATON
4500	4500		LANSING SQUEEZ
4125	4181		LANSING A

RECEIVED  
AUG 08 2011  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA 10 YR\*\* USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: CSG

District: 01

Signed Ken Jehlik  
(TECHNICIAN)

RECEIVED  
JUL 28 2011  
KCC DODGE CITY

Form CS-28