

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-067-20372-00-00  
Spot: SWSWSWNE Sec/Twnshp/Rge: 19-27S-35W  
2789 feet from S Section Line, 2353 feet from E Section Line  
Lease Name: MCCOY B Well #: 2  
County: GRANT Total Vertical Depth: 3110 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	807		WITH 375 SX CMT
PROD	4.5	3109	1015	WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/14/2011 11:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/14/2011 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

**\*\*CASING LEAK 1484-1518\*\*** OBSTRUCTION IN CASING AT 1308'. COULD NOT SPUD THROUGH WITH SINKER BAR. 1ST PLUG CIRCULATE HOLE WITH MUD. PUMP 50 SX CMT AT 840'. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2962	2967		COUNCIL GROVE
2940	2945		COUNCIL GROVE
2923	2928		COUNCIL GROVE
2904	2912		COUNCIL GROVE
2895	2900		COUNCIL GROVE
2873	2877		COUNCIL GROVE

RECEIVED  
AUG 08 2011


KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED

JUL 28 2011

KCC DODGE CITY

Form CD-273