

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00818-00-00
Spot: SWSE Sec/Twnshp/Rge: 12-2S-19W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: ARGAN Well #: 1
County: PHILLIPS Total Vertical Depth: 3425 feet

Operator License No.: 3182
Op Name: NPF ENERGY CORPORATION
Address: PO BOX 3827
TUSTIN, CA 92781

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1535	0	w/900 sxs cmt
PROD	5.5	3390	0	w/200 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/28/2011 9:00 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: PAT COCHRAN Company: NPF ENERGY CORPORATION Phone: (714) 730-7850

Proposed Plugging Method: Ordered 320 sxs 60/40 pozmix - 4% gel - 500# hulls - 8 sxs gel spacer.
Casing leak 1600' - 1700'.
Anhydrite @ 1723'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/28/2011 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Ran tubing in the hole - stacked out at 1892'.
Pulled one joint of tubing.
Pumped 450 sxs 60/40 pozmix - 4% gel with 500# hulls to circulate to surface.
Pulled all tubing.
Hooked to 5 1/2" casing and pumped 60 sxs 60/40 pozmix - 4% gel to circulate cement out of 8 5/8" x 5 1/2" annulus.
S.I.P. 250#.

RECEIVED
AUG 08 2011
KCC WICHITA

Remarks: COPELAND ACID AND CEMENT-TICKET #36917.

Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN)

JUL 29 2011