

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22641-00-02 }
Spot: NESWSE Sec/Twnshp/Rge: 2-10S-21W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: MCCLELLAN Well #: 12
County: GRAHAM Total Vertical Depth: 3875 feet

Operator License No.: 33190
Op Name: NOBLE ENERGY, INC.
Address: 1625 BROADWAY, STE 2200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	211	0	125 SX
PROD	5.5	3874	0	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/21/2011 9:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: JERRY WIRTZ Company: NOBLE ENERGY, INC. Phone: (785) 625-5528

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 10 sxs gel spacer.
Casing leak at 2415' - 2830'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/21/2011 11:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Ran tubing to 2402' - pumped 150 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 1703' - pumped 110 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing. Hooked to 5 1/2" casing and pumped 50 sxs 60/40 pozmix - 4% gel.
S.I.P. 200#.
Hooked to 8 5/8" x 5 1/2" annulus. Pressured to 300# immediately.

RECEIVED
AUG 08 2011
KCC WICHITA

Remarks: BASIC ENERGY SERVICES L.P.-TICKET #04425A.

Plugged through: TBG

District: 04

Signed

Pat Bedore
(TECHNICIAN)

CM