

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23729-00-00
Spot: NESWSESW Sec/Twnshp/Rge: 27-13S-13W
567 feet from S Section Line, 1943 feet from W Section Line
Lease Name: D. REINHARDT Well #: 27-1
County: RUSSELL Total Vertical Depth: 3342 feet

Operator License No.: 6246
Op Name: BENNETT & SCHULTE OIL CO., A GEN
Address: 140 W WICHITA AVE
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	221		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/29/2011 12:00 AM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: DOUG Company: BENNETT & SCHULTE OIL CO. Phone: (785) 483-2721

Proposed Plugging Method: Ordered 140 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RAY DINKEL WitnessType: NONE
Date/Time Plugging Completed: 07/29/2011 9:15 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

1st. Plug at 791' w/25 sxs.
2nd. Plug at 425' w/60 sxs.
3rd. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

RECEIVED

AUG 08 2011

KCC WICHITA

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM